


# SEMI-AUTONOMOUS PLANT

## Outcomes

10X ROI in < 6 Months



### Unified Digital Platform

PLCs, DCS, Energy Meters, Quality Systems

### ABOUT THE COMPANY

Leading Asian OPC & PPC Cement Manufacturer



### KEY AREA


- Line Material Handling to Clinkerization
- Grinding Unit
- Packaging
- Clinker Bulk Dispatch
- WHRS
- CPP

### SYSTEMS INTEGRATED

Sr. No	Equipment/Department	Data Sources Integrated
1	Mines	Logbooks, SAP
2	Crusher	DCS, Logbook
3	Raw Material Handling	DCS
4	Raw Mill	DCS
5	Kiln	DCS
6	Coal Mill	PLC
7	Coal Handling	PLC
8	Cooler	DCS
9	Dispatch Operation	SAP
10	CPP (Captative Power Plant)	DCS
11	WHR (Waste Heat Recovery)	DCS
12	Quality	Excel Report
13	Maintenance	SAP, Logbook
14	Grinding	PLC
15	EMS Line 1	PLC & Energy Meter
16	EMS Line 2	PLC
17	EMS Line 3	PLC
18	EMS CPP	PLC
19	EMS WHRS	Energy Meter



## The 99% Trust Loop



# 1 Equipment + Process Contextualization

## Unifying the Digital Nervous System

To eliminate silos, we did not just install sensors; we integrated the entire operational landscape into a Unified Digital Platform – PlantOS™

- **Scope:** 10 Functional Areas digitalized, from Mines and Crushers to Kilns and Dispatch.
- **Integration:** 19 Integrated Systems including PLCs, DCS, Energy Meters, and Quality Systems.
- **Critical Equipment:** Raw Mills, Coal Mills, Coolers, WHRS, and Captive Power Plants (CPP).
- **The Difference:** Unlike competitors who only sell sensors, PlantOS™ ingested data from logbooks, SAP, and existing DCS/PLC infrastructure to create a complete context for the AI.

# 2 Prediction (The Intelligence)

## Physics-Based Precision

With the data contextualized, the "Physics + AI" layer began monitoring for anomalies with extreme precision.

Scale: 492 critical KPIs monitored across the plant.

Scope: Full coverage of Line Material Handling to Clinkerization.

# 3 Prescription (The Action)

From "What is wrong?" to "Fix this now."

Moving beyond predictive alerts, Star Cement utilized AI-assisted Decision Making.

PlantOS™ provided specific Diagnostic Reports that prescribed exact interventions.

Instead of vaguely identifying issues, the system offered specific recommendations (Diagnostic → Recommendation → Action)



# 4 Guaranteed, User-Validated Outcomes

## The 99% Trust Loop in Action

The ultimate measure of the semi-autonomous plant is the outcome. These results are not estimates; they are User-Validated by Star Cement's own engineering & operations teams.

### Reliability Outcomes

Unplanned Downtime:  
Prevented 46 hours of  
unscheduled downtime

### Production Outcomes

- Throughput: Raised throughput by 10 TPH (Tons Per Hour).
- Production Preserved: Saved 600 Tons of production that would have otherwise been lost.

### Efficiency & Sustainability Outcomes

- Energy Efficiency: Saved 920,000 kcal in Specific Heat Consumption (SHC).
- ROI: Achieved a 10x Return on Investment in less than 6 months.



The **biggest** change was the immediate establishment of a **single source of truth**.  
We moved from *reactive chaos* to *proactive control*.

-Mr. Dhawan Soni, E&I Head, Star Cement

Annual Savings  
**₹47.8 Million (~ \$ 536,340 USD)**

Click to Play

**INFINITE UPTIME** 03 Sept 2025 - 7:34pm  
**Process Diagnostic Report**  
Plant: Star-Cement IUSERV115905709

**Report Status:** COMPLETED **Completed On:** 10 Sept 2025 - 7:42am

**Observation**  
Frequent mill tripping due to high vibration

**Diagnostic**  
High moisture in CFA (10 to 20%)

**Recommendation**  
Utilising less moisture (<10%) CFA for maximum mill output. Covered material transport to shed for ensuring no additional moisture is being added.

**Business Impact**  
Increased mill throughput (5-10 tph).

**Corrective Actions Taken**  
Mail has been sent to concern to cover the material while unloading and transportation of material

**Before Repair** **After Repair**

**Attachments**  
No attachments were uploaded for this report.

**Customer Comments**  
Covering of material while rake unloading has been communicated to RMH dept. In plant dedicated sheds are already in place.

**Completed By:** @starcement.co.in

**INFINITE UPTIME** 14 Oct 2025 - 11:48am  
**Process Diagnostic Report**  
Plant: Star-Cement IUSERV355217526

**Report Status:** COMPLETED **Completed On:** 27 Oct 2025 - 10:42am

**Observation**  
Kiln stopped from 23:05 PM (07:10:25) to 1:30 AM (08:10:25)

**Diagnostic**  
Kiln roller-3 bearing (462PUG) temperature rises from 30 to 60 Deg. C leading to kiln Main Drive tripping.

**Recommendation**  
1. Inspect and maintain kiln roller bearings lubrication oil level. 2. Insure proper circulation and low temperature of cooling water. 3. Maintain kiln shell temperature <250 deg. C.

**Business Impact**  
Production Savings: 1000 T Breakdown Hours Savings: ~2-3 Hours SHC Savings: 20-50 kcal/kg clinker

**Corrective Actions Taken**  
lubrication oil replaced, fresh water circulation for bearing cooling.

**Before Repair** **After Repair**

**Attachments**  
No attachments were uploaded for this report.

**Customer Comments**  
Roller lubrication oil replaced. Fresh water circulation after draining recirculated water for roller bearing cooling.

**Completed By:** @starcement.co.in

**Ready to close the Trust Loop in your facility?**

Infinite Uptime is currently delivering results for **844 plants in 26 countries**

Click Here to

**Try PlantOS™ Today**